

March 4, 2021

via email

SAFSTOR REAL ESTATE CO, LLC
c/o W&A ENGINEERING
355 Oneta Street
Suite D100
Athens, Georgia 30601

Attention: Mr. Jim Burtt
Project Manager

**Regarding: SWM AREA EVALUATION & ON-SITE WASTEWATER
MANAGEMENT EVALUATION SERVICES
PROPOSED SELF-STORAGE FACILITY
471 ELIZABETH AVENUE
FRANKLIN TOWNSHIP, SOMERSET COUNTY, NEW JERSEY
WHITESTONE PROJECT NO.: GJ2117698.000**

Dear Mr. Burtt:

Whitestone Associates, Inc. (Whitestone) has completed a stormwater management (SWM) area evaluation and on-site wastewater management evaluation services at the above-referenced site. The results of the evaluation presented below are based on the soil conditions disclosed by the profile pits performed during Whitestone's February 2021 field investigation.

1.0 PROJECT DESCRIPTION

The subject property located at 471 Elizabeth Avenue in Franklin Township, Somerset County, New Jersey currently consists of an undeveloped lot. Based on the January 18, 2021 *Conceptual Grading, Drainage & Utility Plan* prepared by Bohler Engineering NJ, LLC (Bohler), the proposed development will include construction of a three-story, self-storage facility with new pavements, landscaping, SWM area, septic area, and utilities. The SWM facility will be located within the southern portion of the site. The septic area preliminarily is anticipated to be located within the eastern portion of the site. Final details regarding the type, bottom elevation, and size of the proposed SWM/septic facilities have not been established at the time of this report.

2.0 FIELD EXPLORATION

Whitestone's scope of services consisted of conducting an engineering evaluation of the subsurface conditions disclosed by nine profile pits (identified as SPP-1A, SPP-2A, SPP-3 through SPP-6, and offsets SPP-3A, SPP-4A, and SPP-5A). The subsurface tests extended to depths ranging from approximately five feet below ground surface (fbgs) to 8.5 fbgs. The subsurface tests were located in the field using normal taping procedures and estimated right angles from existing features and are presumed

Other Office Locations:

CHALFONT, PA
215.712.2700

SOUTHBOROUGH, MA
508.485.0755

ROCKY HILL, CT
860.726.7889

WALL, NJ
732.592.2101

PHILADELPHIA, PA
215.848.2323

to be accurate within a few feet. Upon completion, the test locations were backfilled to existing surface levels using soils generated during excavation of the test pits. Soil profile pits and associated infiltration testing performed for the proposed septic system were witnessed by a representative of the Franklin Township Health Department.

3.0 SWM AREA TEST RESULTS

General: The SWM area investigation included four profile pits (identified as SPP-4, SPP-5, and associated offsets SPP-4A and SPP-5A for basin flood testing) performed within the anticipated location of the SWM area. The test locations are shown on the *Test Location Plan* included as Figure 1. Details of the subsurface materials encountered are presented on the *Records of Subsurface Exploration* presented in Appendix A.

Estimated Seasonal High Groundwater Levels: The methods used in determining the estimated seasonal high groundwater (ESHGW) level include evaluating the soil morphology within a test location and identifying irregular spots or blotches of different colors or minerals unlike that of the surrounding soils (mottles). Mottling is the result of the oxidation of minerals within a soil structure as a water level slowly fluctuates.

Groundwater and indications of seasonal high groundwater levels were encountered within the profile pits performed at the depths/elevations indicated in the *Records of Subsurface Exploration*. Groundwater conditions likely will fluctuate seasonally and following periods of precipitation.

Infiltration Testing: Basin flood tests were conducted within the weathered rock/bedrock strata encountered at profile pits SPP-4A and SPP-5A. The basin flood tests performed within the profile pits were conducted in general accordance with the *New Jersey Stormwater Best Management Practices Manual* (BMP Manual). The results of the in-situ testing indicated that basin flood tests did not drain the required 12 inches within 24 hours of filling. Therefore, per the BMP Manual, the limiting zone is considered to be a massive rock substratum and a infiltration rate cannot be assigned. Detailed in-situ infiltration test results are available in Appendix C.

Additionally, representative samples within profile pits SPP-4 and SPP-5 were subjected to tube permeameter analysis as detailed in *New Jersey Stormwater Best Practices Manual*. Laboratory tube permeameter testing resulted in a infiltration rate of less than 0.2 iph. Individual tube permeameter test results are provided in Appendix B.

4.0 SEPTIC AREA TEST RESULTS

General: The septic area investigation included four profile pits (identified as SPP-1A, SPP-2A, SPP-3 and associated offset SPP-3A for basin flood testing) performed within the potential locations of the septic disposal bed areas. The test locations are shown on the *Test Location Plan* included as Figure 1. Details of the subsurface materials encountered are presented on the *Records of Subsurface Exploration* presented in Appendix A.

Estimated Seasonal High Groundwater Levels: Groundwater and indications of seasonal high groundwater levels were encountered within the profile pits performed at the depths/elevations indicated in the *Records of Subsurface Exploration*. Groundwater conditions likely will fluctuate seasonally and following periods of precipitation.

Infiltration Testing: A pit-bailing test was conducted within the weathered rock strata encountered at profile pit SPP-2A at a depth of approximately eight fbg. The pit-bailing test was conducted in general accordance with the *Standards for Individual Subsurface Sewage Disposal Systems (N.J.A.C. 7:9A)* and was witnessed by a Township of Franklin Health Department representative. The results of the pit-bailing test indicated a permeability rate (K) of approximately 3.4 inches per hour.

Additionally, a basin flood test was conducted at profile pit SPP-3A and tube permeameter testing was conducted at profile pit SPP-3. The basin flood test was conducted within the weathered rock strata encountered within SPP-3A. The basin flood test was conducted in general accordance with the *Standards for Individual Subsurface Sewage Disposal Systems (N.J.A.C. 7:9A)*. The results of the in-situ testing indicated that basin flood test did not drain the required 12 inches within 24 hours of filling. Therefore, the limiting zone is considered to be a massive rock substratum and a permeability rate cannot be assigned. Detailed in-situ permeability test results are available in Appendix C. The laboratory tube permeameter testing conducted for SPP-3 resulted in a permeability rate of less than 0.2 iph. Individual tube permeameter test results are provided in Appendix B.

5.0 CLOSING

Whitestone appreciates the opportunity to be of service to SAFStor Real Estate Co, LLC and W&A Engineering and trusts that this information will be helpful for evaluating the proposed development of this property. Please contact us at (908) 668-7777 to further discuss these findings.

Sincerely,

WHITESTONE ASSOCIATES, INC.



Mudar Khantamr, P.E.
Project Manager



Kevin A. Feath, P.E.
Associate

MK/pwd L:\Job Folders\2021\2117698GJ\Reports and Submittals\17698 SWM&Septic.docx
Enclosures
Copy: Kyle McKenna, P.E., Bohler Engineering NJ, LLC
Laurence W. Keller, P.E., Whitestone Associates, Inc.

FIGURE 1
Test Location Plan

APPENDIX A
Records of Subsurface Exploration

RECORD OF SUBSURFACE EXPLORATION

| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | | | | | | | | | | | |
|---|---------------------------------|---|--|-------------------------|--|-------------------------------|--|---------------------|---|---------------------------|---|---------------------|---|
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | | | | | | | | | | | |
| Surface Elevation: ± 77.0 feet | Date Started: 2/8/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Water Depth Elevation</th> </tr> <tr> <th>(feet bgs) (feet)</th> <th></th> </tr> <tr> <td>During: 6.0 71.0</td> <td style="text-align: right;">▼</td> </tr> <tr> <td>At Completion: --- ---</td> <td style="text-align: right;">▼</td> </tr> <tr> <td>24 Hours: --- ---</td> <td style="text-align: right;">▼</td> </tr> </table> | | Water Depth Elevation | | (feet bgs) (feet) | | During: 6.0 71.0 | ▼ | At Completion: --- --- | ▼ | 24 Hours: --- --- | ▼ |
| Water Depth Elevation | | | | | | | | | | | | | |
| (feet bgs) (feet) | | | | | | | | | | | | | |
| During: 6.0 71.0 | ▼ | | | | | | | | | | | | |
| At Completion: --- --- | ▼ | | | | | | | | | | | | |
| 24 Hours: --- --- | ▼ | | | | | | | | | | | | |
| Termination Depth: 8.5 feet bgs | Date Completed: 2/8/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Estimated Seasonal High</th> </tr> <tr> <th>Groundwater Depth Elevation</th> <th></th> </tr> <tr> <td>(feet bgs) (feet)</td> <td></td> </tr> <tr> <td>At Completion: 4.0 73.0</td> <td></td> </tr> </table> | | Estimated Seasonal High | | Groundwater Depth Elevation | | (feet bgs) (feet) | | At Completion: 4.0 73.0 | | | |
| Estimated Seasonal High | | | | | | | | | | | | | |
| Groundwater Depth Elevation | | | | | | | | | | | | | |
| (feet bgs) (feet) | | | | | | | | | | | | | |
| At Completion: 4.0 73.0 | | | | | | | | | | | | | |
| Proposed Location: Septic | Logged By: CN | | | | | | | | | | | | |
| Excavating Method: Test Pit Excavation | Contractor: LNR | | | | | | | | | | | | |
| Test Method: Visual Observation | Rig Type: PC88MR | | | | | | | | | | | | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|---------|----------------|---|--|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 3 | | | 0 - 3 | FILL | 30" Asphalt Millings | Water Seeping in All Sidewalls 2"/10 Minutes |
| 3 - 6 | | | 3 - 6 | RESIDUAL | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Moist to Wet; Friable; No Roots; >15MM Mottling Starting at 4.0 fbg; Clear Boundary | Mottling @ 4.0 fbg to 8.5 fbg Water Sitting on Weathered Rock |
| 6 - 8.5 | | | 6 - 8.5 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; Mottling; Clear Boundary | |
| | | | 9.0 | | Soil Profile Pit SPP-1A Terminated at a Depth of 8.5 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

RECORD OF SUBSURFACE EXPLORATION

| | | | |
|---|---------------------------------|---|---|
| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | |
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | |
| Surface Elevation: ± 77.0 feet | Date Started: 2/6/2021 | Water Depth Elevation (feet bgs) (feet) | |
| Termination Depth: 8.0 feet bgs | Date Completed: 2/6/2021 | Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | |
| Proposed Location: Septic | Logged By: CN | During: 5.5 71.5 | ▼ |
| Excavating Method: Test Pit Excavation | Contractor: LNR | At Completion: --- --- | ▼ |
| Test Method: Visual Observation | Rig Type: PC88MR | 24 Hours: --- --- | ▼ |
| | | At Completion: 4.0 73.0 | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|---------|----------------|--|--|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 2 | | | 0 - 2 | FILL | 24" Asphalt Millings | Water Seeping in All Sidewalls 2"/10 Minutes 0.0 fbg to 5.0 fbg |
| 2 - 5.5 | | | 2 - 5.5 | RESIDUAL | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Moist to Wet; Friable; No Roots; >15MM Mottling at 4.0 fbg; Clear Boundary | Mottling @ 4.0 fbg Water Sitting on Weathered Rock |
| 5.5 - 8 | | | 5.5 - 8 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; No Mottling; Clear Boundary | |
| | | | 8.0 | | Soil Profile Pit SPP-2A Terminated at a Depth of 8.0 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | SPP-2A Used for Pit Bail Test (PB-1) |
| | | | 9.0 | | | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

RECORD OF SUBSURFACE EXPLORATION

| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | | | | | | | | | |
|---|---|--|--|--|---|----------------------|--|----------------------------|--|-----------------------|--|
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | | | | | | | | | |
| Surface Elevation: ± 77.0 feet | Date Started: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: center;">Water Depth Elevation (feet bgs) (feet)</th> <th style="text-align: center;">Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet)</th> </tr> <tr> <td style="text-align: center;">During: 4.0 73.0 ▼</td> <td></td> </tr> <tr> <td style="text-align: center;">At Completion: --- --- ▼</td> <td></td> </tr> <tr> <td style="text-align: center;">24 Hours: --- --- ▼</td> <td></td> </tr> </table> | | Water Depth Elevation (feet bgs) (feet) | Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | During: 4.0 73.0 ▼ | | At Completion: --- --- ▼ | | 24 Hours: --- --- ▼ | |
| Water Depth Elevation (feet bgs) (feet) | Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | | | | | | | | | | |
| During: 4.0 73.0 ▼ | | | | | | | | | | | |
| At Completion: --- --- ▼ | | | | | | | | | | | |
| 24 Hours: --- --- ▼ | | | | | | | | | | | |
| Termination Depth: 6.0 feet bgs | Date Completed: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">At Completion: 3.8 73.2</td> </tr> </table> | | At Completion: 3.8 73.2 | | | | | | | |
| At Completion: 3.8 73.2 | | | | | | | | | | | |
| Proposed Location: Septic | Logged By: CN | | | | | | | | | | |
| Excavating Method: Test Pit Excavation | Contractor: LNR | | | | | | | | | | |
| Test Method: Visual Observation | Rig Type: PC88MR | | | | | | | | | | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|---------|----------------|--|---------------------------------|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 2.5 | | | 0 - 2.5 | FILL | 30" Asphalt Millings | |
| 2.5 - 4 | S-1 | BAG | 2.5 - 4 | RESIDUAL | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Wet; Friable; No Roots; >15MM Mottling at 3.8 fbgs; Clear Boundary | Bag/Tubes Taken @ 3.0 fbgs |
| 4 - 6 | | | 4 - 7 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; Mottling; Clear Boundary | Water Sitting on Weathered Rock |
| | | | 6.0 | | Soil Profile Pit SPP-3 Terminated at a Depth of 6.0 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | |
| | | | 7.0 | | | |
| | | | 8.0 | | | |
| | | | 9.0 | | | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

RECORD OF SUBSURFACE EXPLORATION

| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | | | | | |
|---|---------------------------------|---|--|---|---------------------------|----------------------------|-----------------------|
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | | | | | |
| Surface Elevation: ± 77.0 feet | Date Started: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: center;">Water Depth Elevation (feet bgs) (feet)</th> </tr> <tr> <td style="text-align: center;">During: 4.0 73.0 ▼</td> </tr> <tr> <td style="text-align: center;">At Completion: --- --- ▼</td> </tr> <tr> <td style="text-align: center;">24 Hours: --- --- ▼</td> </tr> </table> | | Water Depth Elevation (feet bgs) (feet) | During: 4.0 73.0 ▼ | At Completion: --- --- ▼ | 24 Hours: --- --- ▼ |
| Water Depth Elevation (feet bgs) (feet) | | | | | | | |
| During: 4.0 73.0 ▼ | | | | | | | |
| At Completion: --- --- ▼ | | | | | | | |
| 24 Hours: --- --- ▼ | | | | | | | |
| Termination Depth: 6.0 feet bgs | Date Completed: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: center;">Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet)</th> </tr> <tr> <td style="text-align: center;">At Completion: 3.8 73.2</td> </tr> </table> | | Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | At Completion: 3.8 73.2 | | |
| Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | | | | | | | |
| At Completion: 3.8 73.2 | | | | | | | |
| Proposed Location: Septic | Logged By: CN | | | | | | |
| Excavating Method: Test Pit Excavation | Contractor: LNR | | | | | | |
| Test Method: Visual Observation | Rig Type: PC88MR | | | | | | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|---------|----------------|--|---|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 2.5 | | | 0 - 2.5 | FILL | 30" Asphalt Millings | |
| 2.5 - 4 | S-1 | BAG | 2.5 - 4 | RESIDUAL | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Wet; Friable; No Roots; >15MM Mottling at 3.8 fbgs; Clear Boundary | Bag/Tubes Taken @ 3.0 fbgs Water Sitting on Weathered Rock |
| 4 - 6 | | | 4 - 7 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; Mottling; Clear Boundary | |
| | | | 6.0 | | Soil Profile Pit SPP-3A Terminated at a Depth of 6.0 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | |
| | | | 7.0 | | | |
| | | | 8.0 | | | |
| | | | 9.0 | | | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

RECORD OF SUBSURFACE EXPLORATION

| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | | | | | | | | | | | |
|---|---------------------------------|--|--|-------------------------|--|-------------------------------|--|---------------------|------------|----------------|-------------|-----------|-------------|
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | | | | | | | | | | | |
| Surface Elevation: ± 75.0 feet | Date Started: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Water Depth Elevation</th> </tr> <tr> <th>(feet bgs) (feet)</th> <th></th> </tr> <tr> <td>During:</td> <td>NE --- ▼</td> </tr> <tr> <td>At Completion:</td> <td>--- --- ▼</td> </tr> <tr> <td>24 Hours:</td> <td>--- --- ▼</td> </tr> </table> | | Water Depth Elevation | | (feet bgs) (feet) | | During: | NE --- ▼ | At Completion: | --- --- ▼ | 24 Hours: | --- --- ▼ |
| Water Depth Elevation | | | | | | | | | | | | | |
| (feet bgs) (feet) | | | | | | | | | | | | | |
| During: | NE --- ▼ | | | | | | | | | | | | |
| At Completion: | --- --- ▼ | | | | | | | | | | | | |
| 24 Hours: | --- --- ▼ | | | | | | | | | | | | |
| Termination Depth: 6.0 feet bgs | Date Completed: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Estimated Seasonal High</th> </tr> <tr> <th>Groundwater Depth Elevation</th> <th></th> </tr> <tr> <td>(feet bgs) (feet)</td> <td></td> </tr> <tr> <td>At Completion:</td> <td>3.0 72.0</td> </tr> </table> | | Estimated Seasonal High | | Groundwater Depth Elevation | | (feet bgs) (feet) | | At Completion: | 3.0 72.0 | | |
| Estimated Seasonal High | | | | | | | | | | | | | |
| Groundwater Depth Elevation | | | | | | | | | | | | | |
| (feet bgs) (feet) | | | | | | | | | | | | | |
| At Completion: | 3.0 72.0 | | | | | | | | | | | | |
| Proposed Location: Proposed SWM | Logged By: CN | | | | | | | | | | | | |
| Excavating Method: Test Pit Excavation | Contractor: LNR | | | | | | | | | | | | |
| Test Method: Visual Observation | Rig Type: PC88MR | | | | | | | | | | | | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|-------|------------------|--|--|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 1 | | | 0 - 1 | FILL | 12" to 18" Asphalt Millings | |
| 1 - 2 | | | 1 - 2 | TOPSOIL | 6" to 12" Topsoil | |
| 2 - 4 | S-1 | BAG | 2 - 4 | GLACIAL DEPOSITS | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Wet; Friable; Sticky; No Roots; >15MM Mottling at 3.0 fbgs; Clear Boundary | Tubes/Bags Taken @ 2.0 fbgs >15MM Mottling 3.0 fbgs to 6.0 fbgs |
| 4 - 6 | | | 4 - 6 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; Mottling | |
| | | | 6.0 | | Soil Profile Pit SPP-4 Terminated at a Depth of 6.0 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | |
| | | | 7.0 | | | |
| | | | 8.0 | | | |
| | | | 9.0 | | | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

RECORD OF SUBSURFACE EXPLORATION

| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | | | | | | | | | | | |
|---|---------------------------------|--|--|-------------------------|--|-------------------------------|--|---------------------|------------|----------------|-------------|-----------|-------------|
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | | | | | | | | | | | |
| Surface Elevation: ± 75.0 feet | Date Started: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Water Depth Elevation</th> </tr> <tr> <th>(feet bgs) (feet)</th> <th></th> </tr> <tr> <td>During:</td> <td>NE --- ▼</td> </tr> <tr> <td>At Completion:</td> <td>--- --- ▼</td> </tr> <tr> <td>24 Hours:</td> <td>--- --- ▼</td> </tr> </table> | | Water Depth Elevation | | (feet bgs) (feet) | | During: | NE --- ▼ | At Completion: | --- --- ▼ | 24 Hours: | --- --- ▼ |
| Water Depth Elevation | | | | | | | | | | | | | |
| (feet bgs) (feet) | | | | | | | | | | | | | |
| During: | NE --- ▼ | | | | | | | | | | | | |
| At Completion: | --- --- ▼ | | | | | | | | | | | | |
| 24 Hours: | --- --- ▼ | | | | | | | | | | | | |
| Termination Depth: 6.0 feet bgs | Date Completed: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Estimated Seasonal High</th> </tr> <tr> <th>Groundwater Depth Elevation</th> <th></th> </tr> <tr> <td>(feet bgs) (feet)</td> <td></td> </tr> <tr> <td>At Completion:</td> <td>3.0 72.0</td> </tr> </table> | | Estimated Seasonal High | | Groundwater Depth Elevation | | (feet bgs) (feet) | | At Completion: | 3.0 72.0 | | |
| Estimated Seasonal High | | | | | | | | | | | | | |
| Groundwater Depth Elevation | | | | | | | | | | | | | |
| (feet bgs) (feet) | | | | | | | | | | | | | |
| At Completion: | 3.0 72.0 | | | | | | | | | | | | |
| Proposed Location: Proposed SWM | Logged By: CN | | | | | | | | | | | | |
| Excavating Method: Test Pit Excavation | Contractor: LNR | | | | | | | | | | | | |
| Test Method: Visual Observation | Rig Type: PC88MR | | | | | | | | | | | | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|-------|------------------|--|--|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 1 | | | 0 - 1 | FILL | 12" to 18" Asphalt Millings | |
| 1 - 2 | | | 1 - 2 | TOPSOIL | 6" to 12" Topsoil | |
| 2 - 4 | S-1 | BAG | 2 - 4 | GLACIAL DEPOSITS | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Wet; Friable; Sticky; No Roots; >15MM Mottling at 3.0 fbgs; Clear Boundary | Tubes/Bags Taken @ 2.0 fbgs >15MM Mottling 3.0 fbgs to 6.0 fbgs |
| 4 - 6 | | | 4 - 6 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; Mottling | |
| | | | 6.0 | | Soil Profile Pit SPP-4A Terminated at a Depth of 6.0 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | |
| | | | 7.0 | | | |
| | | | 8.0 | | | |
| | | | 9.0 | | | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

RECORD OF SUBSURFACE EXPLORATION

| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | | | | | |
|---|---------------------------------|--|--|---|----------------------------------|-------------------------------------|--------------------------------|
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | | | | | |
| Surface Elevation: ± 74.5 feet | Date Started: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: center;">Water Depth Elevation (feet bgs) (feet)</th> </tr> <tr> <td style="text-align: center;"> During: NE --- ▼ </td> </tr> <tr> <td style="text-align: center;"> At Completion: --- --- ▼ </td> </tr> <tr> <td style="text-align: center;"> 24 Hours: --- --- ▼ </td> </tr> </table> | | Water Depth Elevation (feet bgs) (feet) | During: NE --- ▼ | At Completion: --- --- ▼ | 24 Hours: --- --- ▼ |
| Water Depth Elevation (feet bgs) (feet) | | | | | | | |
| During: NE --- ▼ | | | | | | | |
| At Completion: --- --- ▼ | | | | | | | |
| 24 Hours: --- --- ▼ | | | | | | | |
| Termination Depth: 5.0 feet bgs | Date Completed: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: center;">Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet)</th> </tr> <tr> <td style="text-align: center;"> At Completion: 2.5 72.0 </td> </tr> </table> | | Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | At Completion: 2.5 72.0 | | |
| Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | | | | | | | |
| At Completion: 2.5 72.0 | | | | | | | |
| Proposed Location: SWM | Logged By: CN | | | | | | |
| Excavating Method: Test Pit Excavation | Contractor: LNR | | | | | | |
| Test Method: Visual Observation | Rig Type: PC88MR | | | | | | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|---------|-------------------|--|---|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 1.5 | | | 0 - 1.5 | FILL | 18" Asphalt Millings | |
| 1.5 - 3 | S-1 | BAG | 1.5 - 3 | RESIDUAL | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Moist; Friable; Sticky; No Roots; >15MM Mottling @ 2.5 fbg; Clear Boundary | Tubes/Bag Taken @ 2.0 fbg Mottling from 2.5 fbg to 5.0 fbg |
| 3 - 5 | | | 3 - 5 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; Mottling | |
| | | | 5.0 | | Soil Profile Pit SPP-5 Terminated at a Depth of 5.0 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | |
| | | | 6.0 | | | |
| | | | 7.0 | | | |
| | | | 8.0 | | | |
| | | | 9.0 | | | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

RECORD OF SUBSURFACE EXPLORATION

| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | | | | | | | | | | | | | |
|---|---|--|--|--|---|--|----------------------|--|--|------------------------------|--|--|-------------------------|--|--|
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | | | | | | | | | | | | | |
| Surface Elevation: ± 74.5 feet | Date Started: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: center;">Water Depth Elevation (feet bgs) (feet)</th> <th colspan="2" style="text-align: center;">Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet)</th> </tr> <tr> <td style="text-align: center;">During: NE --- ▼</td> <td colspan="2"></td> </tr> <tr> <td style="text-align: center;">At Completion: --- --- ▼</td> <td colspan="2"></td> </tr> <tr> <td style="text-align: center;">24 Hours: --- --- ▼</td> <td colspan="2"></td> </tr> </table> | | Water Depth Elevation (feet bgs) (feet) | Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | | During: NE --- ▼ | | | At Completion: --- --- ▼ | | | 24 Hours: --- --- ▼ | | |
| Water Depth Elevation (feet bgs) (feet) | Estimated Seasonal High Groundwater Depth Elevation (feet bgs) (feet) | | | | | | | | | | | | | | |
| During: NE --- ▼ | | | | | | | | | | | | | | | |
| At Completion: --- --- ▼ | | | | | | | | | | | | | | | |
| 24 Hours: --- --- ▼ | | | | | | | | | | | | | | | |
| Termination Depth: 5.0 feet bgs | Date Completed: 2/6/2021 | At Completion: 2.5 72.0 | | | | | | | | | | | | | |
| Proposed Location: SWM | Logged By: CN | | | | | | | | | | | | | | |
| Excavating Method: Test Pit Excavation | Contractor: LNR | | | | | | | | | | | | | | |
| Test Method: Visual Observation | Rig Type: PC88MR | | | | | | | | | | | | | | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|---------|----------------|--|---|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 1.5 | | | 0 - 1.5 | FILL | 18" Asphalt Millings | |
| 1.5 - 3 | S-1 | BAG | 1.5 - 3 | RESIDUAL | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Moist; Friable; Sticky; No Roots; >15MM Mottling @ 2.5 fbg; Clear Boundary | Tubes/Bag Taken @ 2.0 fbg Mottling from 2.5 fbg to 5.0 fbg |
| 3 - 5 | | | 3 - 5 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; Mottling | |
| | | | 5.0 | | Soil Profile Pit SPP-5A Terminated at a Depth of 5.0 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | |
| | | | 6.0 | | | |
| | | | 7.0 | | | |
| | | | 8.0 | | | |
| | | | 9.0 | | | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

RECORD OF SUBSURFACE EXPLORATION

| Project: Proposed Self-Storage Facility | | WAI Project No.: GJ2117698.000 | | | | | | | | | | | |
|---|---------------------------------|---|--|-------------------------|--|-------------------------------|--|---------------------------|---|--------------------------|---|---------------------|---|
| Location: 471 Elizabeth Avenue; Franklin Township, Somerset County, New Jersey | | Client: SAFStor Real Estate Co, LLC | | | | | | | | | | | |
| Surface Elevation: ± 78.5 feet | Date Started: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Water Depth Elevation</th> </tr> <tr> <th>(feet bgs) (feet)</th> <th></th> </tr> <tr> <td>During: 3.0 75.5</td> <td style="text-align: right;">▼</td> </tr> <tr> <td>At Completion: --- ---</td> <td style="text-align: right;">▼</td> </tr> <tr> <td>24 Hours: --- ---</td> <td style="text-align: right;">▼</td> </tr> </table> | | Water Depth Elevation | | (feet bgs) (feet) | | During: 3.0 75.5 | ▼ | At Completion: --- --- | ▼ | 24 Hours: --- --- | ▼ |
| Water Depth Elevation | | | | | | | | | | | | | |
| (feet bgs) (feet) | | | | | | | | | | | | | |
| During: 3.0 75.5 | ▼ | | | | | | | | | | | | |
| At Completion: --- --- | ▼ | | | | | | | | | | | | |
| 24 Hours: --- --- | ▼ | | | | | | | | | | | | |
| Termination Depth: 5.0 feet bgs | Date Completed: 2/6/2021 | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Estimated Seasonal High</th> </tr> <tr> <th>Groundwater Depth Elevation</th> <th></th> </tr> <tr> <td>At Completion: 3.0 75.5</td> <td></td> </tr> </table> | | Estimated Seasonal High | | Groundwater Depth Elevation | | At Completion: 3.0 75.5 | | | | | |
| Estimated Seasonal High | | | | | | | | | | | | | |
| Groundwater Depth Elevation | | | | | | | | | | | | | |
| At Completion: 3.0 75.5 | | | | | | | | | | | | | |
| Proposed Location: Septic | Logged By: CN | | | | | | | | | | | | |
| Excavating Method: Test Pit Excavation | Contractor: LNR | | | | | | | | | | | | |
| Test Method: Visual Observation | Rig Type: PC88MR | | | | | | | | | | | | |

| SAMPLE INFORMATION | | | DEPTH | HORIZON | DESCRIPTION OF MATERIALS (Classification) | REMARKS |
|--------------------|--------|------|-----------|----------------|---|------------------------------------|
| Depth (feet) | Number | Type | feet | | | |
| | | | 0.0 | | | |
| 0 - 1.5 | | | 0 - 1.5 | FILL | 18" Asphalt Millings | |
| 1.5 - 2.2 | | | 1.5 - 2.2 | TOPSOIL | 8" Topsoil | |
| 2.2 - 3 | S-1 | BAG | 2.2 - 3 | RESIDUAL | Reddish-Brown (5YR 5/4) CLAY LOAM; 10% Gravel; Moderate, Medium Blocky Structure; Wet; Friable; No Roots; No Mottling; Clear Boundary | Tubes/Bags Taken @ 2.5 fbgs |
| 3 - 5 | | | 3 - 5 | WEATHERED ROCK | Dark Reddish-Brown (5YR 4/3) Fractured WEATHERED SHALE; Strong, Coarse Structure; Moist; Very Hard; No Roots; Mottling | Mottling from 3.0 fbgs to 5.0 fbgs |
| | | | 5.0 | | Soil Profile Pit SPP-6 Terminated at a Depth of 5.0 Feet Below Ground Surface Due to Refusal on Weathered Rock/Bedrock | |
| | | | 6.0 | | | |
| | | | 7.0 | | | |
| | | | 8.0 | | | |
| | | | 9.0 | | | |
| | | | 10.0 | | | |
| | | | 11.0 | | | |
| | | | 12.0 | | | |
| | | | 13.0 | | | |
| | | | 14.0 | | | |
| | | | 15.0 | | | |

APPENDIX B

Laboratory Test Results

Tube Permeameter Test Data

Job Number: GJ2117698.000
Project: Proposed Self-Storage Facility
Client: Safstor Real Estate Co, LLC
Lab Tech: T. Jovanov

Sample ID: _____ **Profile Pit No.:** SPP-3 **Sample No.:** T-1 **Depth:** 3.0'

COUNTY/MUNICIPALITY Franklin Twp, Somerset Co **BLOCK** _____ **LOT** _____

1. **Test Number** 1 **Replicate (letter)** A **Date Collected** 2/6/2021

2. **Material Tested:** _____ **Fill** _____ **Test in Native Soil** _____

3. **Type of Sample:** X **Undisturbed** _____ **Disturbed** _____

4. **Sample Dimensions:** **Inside Radius of Sample Tube, R, in cm** 1.91
Length of Sample, L, in inches 3.50

5. **Bulk Density Determination (Disturbed Samples Only):** N/A

6. **Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams** 0.00

Wt. of Tube Containing Sample _____
Wt. of Empty Tube _____

7. **Sample Volume (L x 2.54 cm./inch x 3.14R²), cc.** 101.30

8. **Bulk Density (Sample Wt./Sample Volume), grams/cc.** 0 > 1.2

9. **Standpipe Used:** X **No** _____ **Yes, Indicate Internal Radius, cm.** N/A

10. **Height of Water Level Above Rim of Test Basin, in inches:**

At the Beginning of Each Test Interval, H1 5.00
At the End of Each Test Interval, H2 4.75

11. **Rate of Water Level Drop (Add additional lines if needed):**

| Time, Start of Test Interval, T1 | Time End of Test Interval T2 | Length of Test Interval, T, Minutes |
|----------------------------------|------------------------------|-------------------------------------|
| | | 92.00 |
| | | 96.00 |
| | | 92.00 |
| | | |

12. **Calculation of Permeability:** $K, (in/hr) = 60 \text{ min/hr} \times r^2/R^2 \times L(in)/T(\text{min}) \times \ln (H1/H2)$ **T=** 93.33

K (in/hr) = 0.12 **Classification:** **K0**

13. **Defects in the Sample (Check appropriate items):**

_____ **None**
 _____ **Soil/Tube Contact** _____ **Large Gravel** _____ **Large Roots**
 _____ **Dry Soil** _____ **Smearing** _____ **Compaction**
 _____ **Other - Specify** _____

Tube Permeameter Test Data

Job Number: GJ2117698.000
Project: Proposed Self-Storage Facility
Client: Safstor Real Estate Co, LLC
Lab Tech: T. Jovanov

Sample ID: _____ **Profile Pit No.:** SPP-3 **Sample No.:** T-1 **Depth:** 3.0'

COUNTY/MUNICIPALITY Franklin Twp, Somerset Co **BLOCK** _____ **LOT** _____

1. **Test Number** 1 **Replicate (letter)** B **Date Collected** 2/6/2021

2. **Material Tested:** _____ **Fill** _____ **Test in Native Soil** _____

3. **Type of Sample:** X **Undisturbed** _____ **Disturbed** _____

4. **Sample Dimensions:** **Inside Radius of Sample Tube, R, in cm** 1.91
Length of Sample, L, in inches 3.25

5. **Bulk Density Determination (Disturbed Samples Only):** N/A

6. **Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams** 0.00

Wt. of Tube Containing Sample _____
Wt. of Empty Tube _____

7. **Sample Volume (L x 2.54 cm./inch x 3.14R²), cc.** 94.07

8. **Bulk Density (Sample Wt./Sample Volume), grams/cc.** 0 > 1.2

9. **Standpipe Used:** X **No** _____ **Yes, Indicate Internal Radius, cm.** N/A

10. **Height of Water Level Above Rim of Test Basin, in inches:**

At the Beginning of Each Test Interval, H1 5.00
 At the End of Each Test Interval, H2 4.99

11. **Rate of Water Level Drop (Add additional lines if needed):**

| Time, Start of Test Interval, T1 | Time End of Test Interval T2 | Length of Test Interval, T, Minutes |
|----------------------------------|------------------------------|-------------------------------------|
| | | 240.00 |
| | | |
| | | |
| | | |

12. **Calculation of Permeability:** $K, (in/hr) = 60 \text{ min/hr} \times r^2/R^2 \times L(in)/T(\text{min}) \times \ln (H1/H2)$ **T=** 240.00

K (in/hr) = 0.00 **Classification:** **K0**

13. **Defects in the Sample (Check appropriate items):**

_____ **None**
 _____ **Soil/Tube Contact** _____ **Large Gravel** _____ **Large Roots**
 _____ **Dry Soil** _____ **Smearing** _____ **Compaction**
 _____ **Other - Specify** _____

Tube Permeameter Test Data

Job Number: GJ2117698.000
Project: Proposed Self-Storage Facility
Client: Safstor Real Estate Co, LLC
Lab Tech: T. Jovanov

Sample ID: _____ **Profile Pit No.:** SPP-4 **Sample No.:** T-1 **Depth:** 2.0'

COUNTY/MUNICIPALITY Franklin Twp, Somerset Co **BLOCK** _____ **LOT** _____

1. **Test Number** 1 **Replicate (letter)** A **Date Collected** 2/6/2021

2. **Material Tested:** _____ **Fill** _____ **Test in Native Soil** _____

3. **Type of Sample:** X **Undisturbed** _____ **Disturbed** _____

4. **Sample Dimensions:** **Inside Radius of Sample Tube, R, in cm** 1.91
Length of Sample, L, in inches 3.50

5. **Bulk Density Determination (Disturbed Samples Only):** N/A

6. **Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams** 0.00

Wt. of Tube Containing Sample _____
Wt. of Empty Tube _____

7. **Sample Volume (L x 2.54 cm./inch x 3.14R²), cc.** 101.30

8. **Bulk Density (Sample Wt./Sample Volume), grams/cc.** 0 > 1.2

9. **Standpipe Used:** X **No** _____ **Yes, Indicate Internal Radius, cm.** N/A

10. **Height of Water Level Above Rim of Test Basin, in inches:**

At the Beginning of Each Test Interval, H1 5.00
At the End of Each Test Interval, H2 4.75

11. **Rate of Water Level Drop (Add additional lines if needed):**

| Time, Start of Test Interval, T1 | Time End of Test Interval T2 | Length of Test Interval, T, Minutes |
|----------------------------------|------------------------------|-------------------------------------|
| | | 72.00 |
| | | 73.00 |
| | | 69.00 |
| | | |

12. **Calculation of Permeability:** $K, (in/hr) = 60 \text{ min/hr} \times r^2/R^2 \times L(in)/T(\text{min}) \times \ln (H1/H2)$ **T=** 71.33

K (in/hr) = 0.15 **Classification:** **K0**

13. **Defects in the Sample (Check appropriate items):**

_____ **None**
 _____ **Soil/Tube Contact** _____ **Large Gravel** _____ **Large Roots**
 _____ **Dry Soil** _____ **Smearing** _____ **Compaction**
 _____ **Other - Specify** _____

Tube Permeameter Test Data

Job Number: GJ2117698.000
Project: Proposed Self-Storage Facility
Client: Safstor Real Estate Co, LLC
Lab Tech: T. Jovanov

Sample ID: _____ **Profile Pit No.:** SPP-4 **Sample No.:** T-1 **Depth:** 2.0'

COUNTY/MUNICIPALITY Franklin Twp, Somerset Co **BLOCK** _____ **LOT** _____

1. **Test Number** 1 **Replicate (letter)** B **Date Collected** 2/6/2021

2. **Material Tested:** _____ **Fill** _____ **Test in Native Soil** _____

3. **Type of Sample:** X **Undisturbed** _____ **Disturbed** _____

4. **Sample Dimensions:** **Inside Radius of Sample Tube, R, in cm** 1.91
Length of Sample, L, in inches 3.25

5. **Bulk Density Determination (Disturbed Samples Only):** N/A

6. **Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams** 0.00

Wt. of Tube Containing Sample _____
Wt. of Empty Tube _____

7. **Sample Volume (L x 2.54 cm./inch x 3.14R²), cc.** 94.07

8. **Bulk Density (Sample Wt./Sample Volume), grams/cc.** 0 > 1.2

9. **Standpipe Used:** X **No** _____ **Yes, Indicate Internal Radius, cm.** N/A

10. **Height of Water Level Above Rim of Test Basin, in inches:**

At the Beginning of Each Test Interval, H1 4.50
At the End of Each Test Interval, H2 4.49

11. **Rate of Water Level Drop (Add additional lines if needed):**

| Time, Start of Test Interval, T1 | Time End of Test Interval T2 | Length of Test Interval, T, Minutes |
|----------------------------------|------------------------------|-------------------------------------|
| | | 240.00 |
| | | |
| | | |

12. **Calculation of Permeability:** $K, (in/hr) = 60 \text{ min/hr} \times r^2/R^2 \times L(in)/T(\text{min}) \times \ln (H1/H2)$ **T=** 240.00

K (in/hr) = 0.00 **Classification:** **K0**

13. **Defects in the Sample (Check appropriate items):**

_____ **None**
 _____ **Soil/Tube Contact** _____ **Large Gravel** _____ **Large Roots**
 _____ **Dry Soil** _____ **Smearing** _____ **Compaction**
 _____ **Other - Specify** _____

Tube Permeameter Test Data

Job Number: GJ2117698.000
Project: Proposed Self-Storage Facility
Client: Safstor Real Estate Co, LLC
Lab Tech: T. Jovanov

Sample ID: _____ **Profile Pit No.:** SPP-5 **Sample No.:** T-1 **Depth:** 3.0'

COUNTY/MUNICIPALITY Franklin Twp, Somerset Co **BLOCK** _____ **LOT** _____

1. **Test Number** 1 **Replicate (letter)** A **Date Collected** 2/6/2021

2. **Material Tested:** _____ **Fill** _____ **Test in Native Soil** _____

3. **Type of Sample:** X **Undisturbed** _____ **Disturbed** _____

4. **Sample Dimensions:** **Inside Radius of Sample Tube, R, in cm** 1.91
Length of Sample, L, in inches 3.50

5. **Bulk Density Determination (Disturbed Samples Only):** N/A

6. **Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams** 0.00

Wt. of Tube Containing Sample _____
Wt. of Empty Tube _____

7. **Sample Volume (L x 2.54 cm./inch x 3.14R²), cc.** 101.30

8. **Bulk Density (Sample Wt./Sample Volume), grams/cc.** 0 > 1.2

9. **Standpipe Used:** X **No** _____ **Yes, Indicate Internal Radius, cm.** N/A

10. **Height of Water Level Above Rim of Test Basin, in inches:**

At the Beginning of Each Test Interval, H1 5.00
 At the End of Each Test Interval, H2 4.99

11. **Rate of Water Level Drop (Add additional lines if needed):**

| Time, Start of Test Interval, T1 | Time End of Test Interval T2 | Length of Test Interval, T, Minutes |
|----------------------------------|------------------------------|-------------------------------------|
| | | 240.00 |
| | | |
| | | |

12. **Calculation of Permeability:** $K, (in/hr) = 60 \text{ min/hr} \times r^2/R^2 \times L(in)/T(\text{min}) \times \ln (H1/H2)$ **T=** 240.00

K (in/hr) = 0.00 **Classification:** **K0**

13. **Defects in the Sample (Check appropriate items):**

_____ **None**
 _____ **Soil/Tube Contact** _____ **Large Gravel** _____ **Large Roots**
 _____ **Dry Soil** _____ **Smearing** _____ **Compaction**
 _____ **Other - Specify** _____

Tube Permeameter Test Data

Job Number: GJ2117698.000
Project: Proposed Self-Storage Facility
Client: Safstor Real Estate Co, LLC
Lab Tech: T. Jovanov

Sample ID: _____ **Profile Pit No.:** SPP-5 **Sample No.:** T-1 **Depth:** 3.0'

COUNTY/MUNICIPALITY Franklin Twp, Somerset Co **BLOCK** _____ **LOT** _____

1. **Test Number** 1 **Replicate (letter)** B **Date Collected** 2/6/2021

2. **Material Tested:** _____ **Fill** _____ **Test in Native Soil** _____

3. **Type of Sample:** X **Undisturbed** _____ **Disturbed** _____

4. **Sample Dimensions:** **Inside Radius of Sample Tube, R, in cm** 1.91
Length of Sample, L, in inches 2.25

5. **Bulk Density Determination (Disturbed Samples Only):** N/A

6. **Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams** 0.00

Wt. of Tube Containing Sample _____
Wt. of Empty Tube _____

7. **Sample Volume (L x 2.54 cm./inch x 3.14R²), cc.** 65.12

8. **Bulk Density (Sample Wt./Sample Volume), grams/cc.** 0 > 1.2

9. **Standpipe Used:** X **No** _____ **Yes, Indicate Internal Radius, cm.** N/A

10. **Height of Water Level Above Rim of Test Basin, in inches:**

At the Beginning of Each Test Interval, H1 5.00
At the End of Each Test Interval, H2 4.99

11. **Rate of Water Level Drop (Add additional lines if needed):**

| Time, Start of Test Interval, T1 | Time End of Test Interval T2 | Length of Test Interval, T, Minutes |
|----------------------------------|------------------------------|-------------------------------------|
| | | 240.00 |
| | | |
| | | |
| | | |

12. **Calculation of Permeability:** $K, (in/hr) = 60 \text{ min/hr} \times r^2/R^2 \times L(in)/T(\text{min}) \times \ln (H1/H2)$ **T=** 240.00

K (in/hr) = 0.00 **Classification:** **K0**

13. **Defects in the Sample (Check appropriate items):**

_____ **None**
 _____ **Soil/Tube Contact** _____ **Large Gravel** _____ **Large Roots**
 _____ **Dry Soil** _____ **Smearing** _____ **Compaction**
 _____ **Other - Specify** _____

APPENDIX C
Basin Flood Test Data

APPENDIX D
Supplemental Information
(USCS, Terms & Symbols)



UNIFIED SOIL CLASSIFICATION SYSTEM

SOIL CLASSIFICATION CHART

| MAJOR DIVISIONS | | | LETTER SYMBOL | TYPICAL DESCRIPTIONS |
|---|---|--|---------------|--|
| COARSE GRAINED SOILS | GRAVEL AND GRAVELLY SOILS | CLEAN GRAVELS (LITTLE OR NO FINES) | GW | WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES |
| | | GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES) | GP | POORLY-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES |
| | SAND AND SANDY SOILS | CLEAN SAND (LITTLE OR NO FINES) | GM | SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES |
| | | SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES) | GC | CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES |
| MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE | MORE THAN 50% OF COARSE FRACTION <u>RETAINED</u> ON NO. 4 SIEVE | CLEAN SAND (LITTLE OR NO FINES) | SW | WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES |
| | | SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES) | SP | POORLY-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES |
| FINE GRAINED SOILS | SILTS AND CLAYS | LIQUID LIMITS <u>LESS</u> THAN 50 | SM | SILTY SANDS, SAND-SILT MIXTURES |
| | | | SC | CLAYEY SANDS, SAND-CLAY MIXTURES |
| MORE THAN 50% OF MATERIAL IS <u>SMALLER</u> THAN NO. 200 SIEVE SIZE | SILTS AND CLAYS | LIQUID LIMITS <u>GREATER</u> THAN 50 | ML | INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY |
| | | | CL | INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS |
| HIGHLY ORGANIC SOILS | SILTS AND CLAYS | LIQUID LIMITS <u>GREATER</u> THAN 50 | OL | ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY |
| | | | MH | INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS |
| HIGHLY ORGANIC SOILS | SILTS AND CLAYS | LIQUID LIMITS <u>GREATER</u> THAN 50 | CH | INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS |
| | | | OH | ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS |
| HIGHLY ORGANIC SOILS | | | PT | PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS |

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS FOR SAMPLES WITH 5% TO 12% FINES

GRADATION*

% FINER BY WEIGHT

TRACE..... 1% TO 10%
LITTLE..... 10% TO 20%
SOME..... 20% TO 35%
AND..... 35% TO 50%

COMPACTNESS*
Sand and/or Gravel

RELATIVE DENSITY

LOOSE..... 0% TO 40%
MEDIUM DENSE.... 40% TO 70%
DENSE..... 70% TO 90%
VERY DENSE..... 90% TO 100%

CONSISTENCY*
Clay and/or Silt

RANGE OF SHEARING STRENGTH IN POUNDS PER SQUARE FOOT

VERY SOFT..... LESS THAN 250
SOFT..... 250 TO 500
MEDIUM..... 500 TO 1000
STIFF..... 1000 TO 2000
VERY STIFF..... 2000 TO 4000
HARD..... GREATER THAN 4000

* VALUES ARE FROM LABORATORY OR FIELD TEST DATA, WHERE APPLICABLE. WHEN NO TESTING WAS PERFORMED, VALUES ARE ESTIMATED.

L:\Geotechnical Forms and References\Reports\USCSTRMSSYM NJ.docx

Other Office Locations:

CHALFONT, PA
215.712.2700

SOUTHBOROUGH, MA
508.485.0755

ROCKY HILL, CT
860.726.7889

WALL, NJ
732.592.2101

PHILADELPHIA, PA
215.848.2323

GEOTECHNICAL TERMS AND SYMBOLS

SAMPLE IDENTIFICATION

The Unified Soil Classification System is used to identify the soil unless otherwise noted.

SOIL PROPERTY SYMBOLS

- N: Standard Penetration Value: Blows per ft. of a 140 lb. hammer falling 30" on a 2" O.D. split-spoon.
 Qu: Unconfined compressive strength, TSF.
 Qp: Penetrometer value, unconfined compressive strength, TSF.
 Mc: Moisture content, %.
 LL: Liquid limit, %.
 PI: Plasticity index, %.
 δd: Natural dry density, PCF.
 ▽: Apparent groundwater level at time noted after completion of boring.

DRILLING AND SAMPLING SYMBOLS

- NE: Not Encountered (Groundwater was not encountered).
 SS: Split-Spoon - 1 3/8" I.D., 2" O.D., except where noted.
 ST: Shelby Tube - 3" O.D., except where noted.
 AU: Auger Sample.
 OB: Diamond Bit.
 CB: Carbide Bit
 WS: Washed Sample.

RELATIVE DENSITY AND CONSISTENCY CLASSIFICATION

| <u>Term (Non-Cohesive Soils)</u> | <u>Standard Penetration Resistance</u> |
|----------------------------------|--|
| Very Loose | 0-4 |
| Loose | 4-10 |
| Medium Dense | 10-30 |
| Dense | 30-50 |
| Very Dense | Over 50 |

| <u>Term (Cohesive Soils)</u> | <u>Qu (TSF)</u> |
|------------------------------|-----------------|
| Very Soft | 0 - 0.25 |
| Soft | 0.25 - 0.50 |
| Firm (Medium) | 0.50 - 1.00 |
| Stiff | 1.00 - 2.00 |
| Very Stiff | 2.00 - 4.00 |
| Hard | 4.00+ |

PARTICLE SIZE

| | | | | | |
|----------|-------------|-------------|---------------|------|-----------------|
| Boulders | 8 in.+ | Coarse Sand | 5mm-0.6mm | Silt | 0.074mm-0.005mm |
| Cobbles | 8 in.-3 in. | Medium Sand | 0.6mm-0.2mm | Clay | -0.005mm |
| Gravel | 3 in.-5mm | Fine Sand | 0.2mm-0.074mm | | |

L:\Geotechnical Forms and References\Reports\USCSTRMSSYM NJ.docx

Other Office Locations:

CHALFONT, PA
215.712.2700

SOUTHBOROUGH, MA
508.485.0755

ROCKY HILL, CT
860.726.7889

WALL, NJ
732.592.2101

PHILADELPHIA, PA
215.848.2323